



### ITO Metro Station, New Delhi of Delhi Metro Rail Corporation Ltd

#### S.A.Verma, General Manager, DMRC



PARIS- 15 November 2017





## **Stakeholders**

Project Owner : Delhi Metro Rail Corporation Ltd.

Principal Stakeholders: Government of India Government of Delhi Japan International Cooperation Agency (JICA)

Contractor Designer : L&T- SUCG JV : Mott MacDonald Pvt Ltd





### ITO Metro Station during construction







PARIS- 15 November 2017





## **Project Description**

Area:19345 sqmLocation:ITO JunctionDepth:18 mConstruction method:Top downTime taken in project completion:30 monthsFootfall:24,000 per dayProject Cost:€ 26.55 Million

Constructed directly beneath one of the busiest intersections of Delhi (175,000 PCUs per day)







## **Short film on ITO Metro Station**

DMRC ITO Metro Station.mp4



PARIS- 15 November 2017





## **Spheres of Sustainability**

Environment Air, Water, Material, Energy, Waste

**Sustain** 

-ability

Social Community, Standard of living, Education Economic Profit, Cost savings, Economic growth




PARIS- 15 November 2017





### **Environment- Measures Adopted**





PARIS- 15 November 2017





**Air Quality Management during construction Monitoring of Particulate Matter during construction** ≻Parameter- PM<sub>10</sub> **Frequency-** Fortnightly Third party monitoring Measures taken to minimize dust Proper barricading Water sprinkling Dust collector at batching plant Covering of muck during transportation Use of Green net Toe dust cleaning







### **Air Quality Management during operation**

# Provision of MERV -8 filters CO2 sensors





PARIS- 15 November 2017





#### Water conservation during construction

- Provision for recharge of dewatered water through recharge pit
- Reuse of curing water

Use of RO reject for dust suppression, wheel washing and in toilets







#### Water conservation during operation

- Rain water harvesting
- Water meters at all significant installations
- Adequate maintenance of cooling tower to reduce water loss
- AHU filter cleaning through proper tanks/ vacuum plants









#### **Reduction in water consumption**

Station	Water consumption	Remarks
Phase-ll stations	17937 KL	Average of Phase-II stations having similar area
ITO	16000 KL	Reduction of 11%



PARIS- 15 November 2017

AITES





### Resource (Material) Conservation during construction

- <u>10% recycled materials used in construction</u>
- <u>85% materials procured locally minimizing Carbon foot print during transportation</u>
- Use of Fly-ash



PARIS- 15 November 2017





#### **10% recycled materials used in construction**

S. No	<b>Civil Material Description</b>	% of Recycled Content
1.	Cement	14
2.	RCC	10
3.	Structural Steel	25
4.	Ceramic tiles	40
5.	Glass	18
6.	Stainless steel Grade 304	25



ITES





## 85% materials procured locally minimizing Carbon foot print during transportation.

Material	Place and Distance from project site	
Glass	Canon (Rajasthan) – 230 Km, Cement – Ultratech plant location	
Coarse Sand	Shree Balaji ( Adarsh Nagar, Delhi ) 25 Km	
Fine Sand	Abycon ( Haryana) – 198 Km	
Stone aggregates	Ultratect ( Adarsh Nagar, Delhi) 25 Km	
Stainless steel	Gurgaon Plant (Haryana)- 43 Km	
RCC	Sarai Kale Khan (Delhi)- 8km	



PARIS- 15 November 2017





### **Use of Fly ash**

## Approx <u>100 MT</u> of Fly ash has been used during construction





PARIS- 15 November 2017





#### Waste management

Approx <u>97%</u> Construction & Demolition waste recycles and remaining <u>3%</u> reused at site itself.









# 88% of waste produced was diverted away from landfill site





PARIS- 15 November 2017





#### **Energy conservation measures**

- <u>9 kWp</u> Solar PV installed at station premises
- LED lighting
- Energy efficient HVAC
- Provision of regenerative braking system in Lifts









## **Energy Conservation**

#### Reduction in Energy Consumption

Station	Energy consumption per sqm	% variation
Average of Phase-II stations having similar area	236	
ITO	112	- 52%



PARIS- 15 November 2017





## **Social Approach**

Care for

**Employees** 

Service provider (Transport) Footfall- 24,000 per day

> Designed for differently abled commuters

Education and training

Art and Culture



PARIS- 15 November 2017





## **Service Provider**

Footfall : <u>24,000 per day</u>
Benefits achieved
a) Reduction in traffic congestion
b) Reduction in road accidents
c) Reduction in travel time
d) Reduction in noise and air pollution



ES PARIS- 15 November 2017



>



#### **Designed for differently abled commuters**

- Reserved parking
- Provision of wheel chairs
- Staff Assistance
- All lifts equipped with wide access doors, Handrail & control buttons at convenient height
  - Specially designed AFC gates
  - Ramps to maintain uniformity in floor levels
  - Low height ticket counters
  - Dedicated toilets
    - Tactile path from all entrances/exit points of the station, along warning strip on the platform edge
  - Braille buttons inside and outside the lifts
  - Directional information and signage







## **Art and Culture**

- Since the corridor passes through areas of historical importance, the station has been decorated with panels and artworks depicting the glory of the bygone era.
- During construction, adequate care was taken to ensure that the monuments nearby were not harmed in any way by Metro construction.
- Construction only began after taking clearance from the National Monuments Authority











## **Economical Benefits**


Direct Earning from commuters

#### Indirect

Improved accessibility , landing to better job opportunities, increase in real estate cost along corridor Cost savings due time saving, reduction in fuel consumption etc







➢ Project cost- 26.55 Million Euro

Earning per day- 3,588 Euro
Indirect benefits

Employment- 500+ during construction & 30 during operation
 Other benefits from all operational corridors of DMRC

Descriptors	2016 (In Million Euro)
Cost of saved time by metro passengers	861
Cost of savings in fuel	463
Saving of Vehicles (capital + Operating) cost	556
Cost of less pollution saved	108
Cost of accident saved	14
Cost of time saved due to decongestion	103
Cost of saved in annual infrastructure maintenance	7
Total Cost of all Benefits	2112









## **Green Building Certification**

ITO Metro Station has been awarded with **"Platinum"** Rating – the highest Green Building rating by Indian Green Building Council (IGBC).





PARIS- 15 November 2017





## Climate change is a pressing global challenge. It calls for a collective human action and a comprehensive response. The issue is not merely about climate change; it is about climate justice.

## Narendra Modi Prime Minister of India



AITES PARIS- 15 November 2017





## **Thank You!**



AITES





PARIS- 15 November 2017

S.A. Verma, General Manager (Environment)